

8-17

93

6 070938

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,401-00-00
50' N
SW SE NE, SEC. 14, T 14 S, R 27 WE
3020 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Rhoades Well # 1

Operator: Bankoff Oil Company

County Gove 141.31

Name & Address 100 S. Market #203 A

Well Total Depth 4348 feet

Wichita, Kansas 67202

Conductor Pipe: Size 0 feet

Frank Mize

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 17th Month: August Year: 19 91

Plugging proposal received from Gary Fisher

(company name) Abercrombie Drilling, Inc. (phone) _____

were: 8 5/8" 310' S.P. cwc. w/200 sx. 60/40 Poz. - 2% Gel. - 3% C.C. by Allied Cement.

Elv. 2512' - Anhy. 1953' - Miss well. Mud condition 45 vis. - 9.2 Wt. - 10 W.L.

No circulation problems. Proposal 190 sx. 60/40 poz. 6% gel. - 3% C.C. w/1 sk. flocele.

Circulate hole. Spot with drill stem. Heavy mud between all plugs.

25 sk. @ 1960 - 100 sk. w/1sk. F.C. @ 985' - 40sk. @ 360' - 10sk. @ 40'. 15 sks. in

rathole (circulate) Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: A.M. Day: 17th Month: August Year: 19 91

ACTUAL PLUGGING REPORT Bankoff ordered 190 sx. 60/40 poz. - 6% gel. - 3% C.C. - 1 sk.

flocele. Spotted with drill stem, heavy mud between all plugs.

1st plug 25 sx. @ 1960'. 15 sx. in Rathole (Circulate)

2nd plug 100 sx. w/1 sk. F.C. @ 985'.

3rd plug 40 sx. @ 360'.

4th plug 10 sx. @ 40'.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1991

Remarks: Cemented by: Allied Cement.

INVOICED

DATE 9-12-91

INV. NO. 33084

Giles S.

Signed *Marion J. Schmidt* (TECHNICIAN)