

4 050061

10-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION,
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,349-00-00

SE SW SW, SEC. 5, T14 S, R 27 W/E

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Jamison Trust Well # 1

Operator: Ritchie Exp Inc.

County Gove 143.00

Name & Address 125 N. Market Suite 1000

Well Total Depth 4400 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

316-267-4375

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor White and Ellis Drilling Inc. License Number 5420

Address

Company to plug at: Hour: PM Day: 25 Month: Oct. Year: 19 90

Plugging proposal received from Don Demel

(company name) (phone)

were: Order 190 sks 60/4 poz 6% gel w/ 1/2 lb f.c. per sk and 8 5/8 wiper plug.

Spot all plugs thru drill pipe with heavy mud between all plugs.

Plugging Proposal Received by Marvin Miller (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 5:15PM Day: 25 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT

1st plug at 2025 w/25 sks

OCT 31 1990

2nd plug at 1040 w/100 sks

10-31-90

3rd plug at 300 sks w/40 sks

4th plug at 40 w/10 sks and 8 5/8 wiper plug.

15 sks in rathole

Remarks: Cemented by Allied. Elevation 2564 Anhy 2010 - 48 No Arb.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 11-6-90

INV. NO. 29847

File S.

Signed Marvin Miller (TECHNICIAN)

Marvin Miller