

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and file ONE Copy)

API # 15-063-21,472-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR BLACK PETROLEUM COMPANY KCC LICENSE # 30407  
ADDRESS P.O. BOX 12922 (owner/company name) CITY WICHITA (operator's)

STATE KANSAS ZIP CODE 67277-2922 CONTACT PHONE # (316) 942-2741

LEASE BALZERICK WELL# #1 SEC. 13 T. 14S R. 27 (East/West)  
150' N of E/2 SE NE SPOT LOCATION/QQQQ COUNTY GOVE

3450' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 8 5/8" SET AT 225' CEMENTED WITH 60-40 posmix-160 SACKS

PRODUCTION CASING SIZE            SET AT            CEMENTED WITH            SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:           

ELEVATION 2518'/2523' T.D. 4385' PBD            ANHYDRITE DEPTH 1973'-2017'  
(G.L./K.E.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2010' w/25 sx; 2nd plug @ 1000'  
w/100 sx; 3rd plug @ 265' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx; Total 190  
sx 60-40 posmix 6% gel 1/4# Floseal per sk.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACC-1 FILED? No

If not explain why? Sent to Operator to complete

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# (913) 743-5443

ADDRESS 533 N. Main City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684  
(company name) (contractor's)

ADDRESS 150 N. Main, Ste 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Complete at 11:30 a.m. 3-18-94

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-29-94 AUTHORIZED OPERATOR/AGENT: *[Signature]*  
(signature)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 31 1994  
CONSERVATION DIVISION  
Wichita, Kansas