

15-169-00797-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline County, Sec. 24 Twp. 14 Rge. ~~3E~~ 3 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Kansas Drilling Co.

Lease Name Anderson Well No. 1

Office Address Box 229 - McPherson, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 10-26-53 19

Application for plugging filed 9-25-53 19

Application for plugging approved 9-25-53 19

Plugging commenced 9-30-53 19

Plugging completed 9-30-53 19

Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3271 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	145'	Cemented
				5 1/2"	3269'	900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from 3271' to 3260' with wet sand and then with 6 sacks cement.

Ran a bridge at 140' and 15 sacks cement. Filled solid with mud to below surface of ground and then filled to top with 5 sacks cement.

10-27-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kansas Drilling Co.

Address Box 229 - McPherson, Kansas.

STATE OF KANSAS, COUNTY OF McPHERSON, ss.

Gordon T. Adams d/b/a/ Kansas Drlg. Co. (Employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. KANSAS DRILLING COMPANY

(Signature) By: Gordon T. Adams

Box 229 - McPherson, Kansas. (Address)

SUBSCRIBED AND SWORN to before me this 26th day of October, 19 53.

My commission expires Feb. 23, 1955

Jeanette Adams Notary Public.

23-8390-4 6-51-20M

PLUGGING
FILE SEC 24 T 14 R 34
BOOK PAGE 130 LINE 20

15-169-00797-00-00

WELL Andersen NO. 1

LOCATION: ^{SE} ~~NE~~/₄ of NE/₄ of NE/₄
Sec. 24, Twp. 14, R. 3W
Saline County, Kansas.

COMPANY Northwestern Drilling Co.

COMMENCED 10-15-52

COMPLETED 10-26-52

CASING RECORD:

145' of 8-5/8" set with 150 sacks cement.
3269' of 5 1/2" set with 150 sacks cement.

LOG:

Sand	70
Shale	135
Anhydrite	165
Lime	700
Shale & lime	1300
Shale & shells	1535
Lime	1640
Shale & lime	2535
Shale	2625
Lime	2890
Shale	3045
Lime	3110
Shale & lime	3195
Shale	3205
Shale	3269 TD.

PLUGGING
 FILE SEC 24 T 14 R 34
 BOOK PAGE 130 OF 20