

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD *1-2*  
K.A.R.-82-3-117

API NUMBER 15-051-23892-00-00

LEASE NAME Schumacker #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE NW SW/4

SEC. 23 TWP. 14S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 8/13/84

Plugging Completed 8/29/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Oil Producers Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Ks. 67208

PHONE # (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3554'

Show depth and thickness of all water, oil and gas formations.

**WELL, GAS OR WATER RECORDS**

**CASING RECORD**

| Formation | Content | From | To | Size           | Put in | Pulled out    |
|-----------|---------|------|----|----------------|--------|---------------|
|           |         |      |    | 8 5/8<br>4 1/2 | 3553'  | none<br>2108' |
|           |         |      |    |                |        |               |
|           |         |      |    |                |        |               |
|           |         |      |    |                |        |               |

Describe in detail the manner in which the well was plugged, indicating where  
the mud fluid was placed and the method or methods used in introducing it into  
the hole. If cement or other plugs were used state, the character of same and  
depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged bottom with 4 sacks cement, sand to 3442' & 4 sacks cement. Shot pipe at  
3006', 2717', 2409', & 2108'. Pulled 63 joints of pipe. Plugged well with 5 hulls,  
5 gel, 50 cement, 10 gel, 70 cement, 4 hulls, plug, & 70 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or  
operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements and matters herein contained and  
the log of the above-described well, and the same are true and  
correct, so help me God.

SEP 06 1984

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

CONSERVATION DIVISION  
SUBSCRIBED AND SWORN TO before me this 4th day of Sept., 1984



Irene Hoover  
Notary Public

Commission expires: \_\_\_\_\_