

15-051-23113-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 22 Twp. 14 Rge. 17 E/W
Location as "NE/CNW/SW" or footage from lines
SW SE NE

Lease Owner Eagle Oil Company
Lease Name Hertel Bros. Well No. #1
Office Address Box 295 Victoria, Kansas 67671


Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 8-18- 1982
Application for plugging filed 8-18- 1982
Application for plugging approved 8-18- 1982
Plugging commenced 1:15 pm 8-18- 1982
Plugging completed 4:15 pm 8-18- 1982
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Butcher
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3600'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

8 5/8 set @ 272'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 700' with heavy mud and mixed 80 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 300' with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 40' built solid bridge pushed down plug and mixed 10 sacks and filled hole to bottom of cellar; mixed 10 sacks and poured into the rat hole.

All cement used was 50-50 Poz Mix 4% Gel
(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., Inc. License # 5671

STATE OF Kansas COUNTY OF Russell, ss.
Stanley C. Lingreen (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen
Box 293 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1982

My commission expires November 10, 1984

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

DEC 21 1982
12-21-1982
CONSERVATION DIVISION
Wichita, Kansas