

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 35 Twp. 14S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Globe Oil & Refining Co.

Lease Name Dechant Well No. 1

Office Address 301 S. Market, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 12 1957

Application for plugging filed (written) August 13 1957

Application for plugging approved August 12 1957

Plugging commenced August 12 1957

Plugging completed August 12 1957

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3683 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	321	Cem. 200 sxs.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 480'. Sun Oil Well Cementing spotted 25 sacks cement through drill pipe at 480'. 25 sacks at 300' and 10 sacks in top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 915 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Leo Ross (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

301 S. Market, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August 19 57

[Signature]  
Notary Public.

My commission expires July 21, 1958

PLUGGING  
FILE SEC. 35 T. 14 R. 18W  
BOOK PAGE 30 LINE 2

108-14-57

Globe Oil & Refining Co.  
Dechant No. 1  
SW SW SW Sec. 35-14S-18W  
Ellis County, Kansas


Date Commenced: 7-31-57  
Date Completed: 8-12-57  
Drilling Contractor: Lewis Drilling Company  
Total Depth - 3683'  
Dry & Abandoned

<u>Formation</u>	<u>Depth</u>	<u>Casing Record:</u>
Surface	70	8 5/8" 321' Cem. 200 sacks
Shale	321	
Red bed	640	<u>Geological Tops - Schlumberger Log</u>
Sand	865	Heebner 3278'
Red bed	1020	Lansing 3326'
Red bed & shale	1215	Conglomerate 3609'
Anhydrite	1250	Arbuckle 3662'
Red bed & shale	1365	Sch. T.D. 3686'
Shale & shells	1880	
Lime	2350	
Lime & shale	3160	
Lime	3610	
Lime & shale	3635	
Lime	3683	

Driller's log T.D. 3683'  
Schlumberger T.D. 3686'


\*\*\*\*\*

I hereby certify that this is a true and correct log of the above mentioned well.

  
Leo Ross

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a notary public, in and for said County and State this 13th day of August, 1957.

  
Notary Public

My Commission expires July 21, 1958.

PLUGGING
REC. SEC 35 T 14 R 18W
BOOK PAGE 37 LINE 2