

15-051-03920-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County. Sec. 21 Twp. 14 Rge. (E) 18 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW SW SE

Lease Owner WHITE EAGLE OIL COMPANY

Lease Name RANDA Well No. 1

Office Address First National Building Tulsa 3, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-1-51 19

Application for plugging filed Verbal 11-1-51 19

Application for plugging approved " 11-1-51 19

Plugging commenced 11-2-51 19

Plugging completed 11-2-51 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS
Rotary Bushing Elevation 2030'

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	dry	3069	-1039	8-5/8"	904'	none
Heebner		3287	-1257			
Toronto		3307	-1277			
Douglas		3324	-1294			
Lansing		3337	-1307			
Base Kansas City		3576	-1546			
Penn. Basal Conglomerate		3620	-1591			
Arbuckle		3659	-1629			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole full of heavy drilling mud to 240'. Plug and 20 sacks of cement placed at 240', than heavy mud, plug and 10 sacks cement to top.

11-08-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to White Eagle Oil Company % Harry Saye
Address First National Building, Tulsa 3, Oklahoma.

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Harry Saye (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry Saye
First National Building, Tulsa 3, Oklahoma.
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 19 51

My commission expires August 29, 1955. Notary Public.

PLUGGING
FILE SEC 21 T. 14 R. 18 W. 3
BOOK PAGE 14

DRILLER'SLOG

Company: White Eagle Oil Company

NW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$
Sec. 21, Twp. 14S, Rge. 18WFarm: Randa Well No. 1
Comm: 10-17-51 Comp: 11-2-51County: Ellis,
KansasTotal Depth: 3700'
Contractor: Peel Brothers, Inc.

ELEVATION:

Casing: 8 5/8" 900' cem.

PRODUCTION: Dry

Figures below indicate bottom of formations

Clay and Shale	(0)	35
Sand		50
Shale and Sand		290
Shale		900
Shale and Iron		545
Sand and Shale		634
Red Rock and Shale		690
Sand		885
Red Bed		904
Red Bed and Sand		1155
Red Bed and Shale		1237
Anhydrite		1275
Shale and Shells		1820
Sand and Salt		1865
Shale and Shells		1972
Sand (sharp)		1986
Broken Lime and Shale		2090
Shale and Lime Streaks		2240
Shale and Lime		2465
Lime		2588
Lime and Shale		3160
Lime		3190
Lime and Shale		3238
Lime		3595
Lime and Red Shale		3620
Conglomerate		3672
Dolomite		3700
Total Depth		3700

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.,

NOV 13 1951
COMMERCIAL DIVISION
Wichita, KansasMendell L. Peel

SUBSCRIBED AND SWORN to before me this 5th day of November, 1951.

Bernice A. Lavin
Notary Public, Barton County, Ks.

My commission expires April 23, 1955.

DRILLER'S

LOG

Company: White Eagle Oil Company

NW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$
Sec. 21, Twp. 14S, Rge. 18W

Farm: Randa Well No. 1
Comm: 10-17-51 Comp: 11-2-51

County: Ellis,
Kansas

Total Depth: 3700'
Contractor: Peel Brothers, Inc.

ELEVATION:

Casing: 8 5/8" 900' cem.

PRODUCTION: Dry

Figures below indicate bottom of formations

Clay and Shale	(0)	35
Sand		50
Shale and Sand		290
Shale		500
Shale and Iron		545
Sand and Shale		634
Red Rock and Shale		690
Sand		885
Red Bed		904
Red Bed and Sand		1155
Red Bed and Shale		1237
Anhydrite		1275
Shale and Shells		1820
Sand and Salt		1865
Shale and Shells		1972
Sand (sharp)		1986
Broken Lime and Shale		2090
Shale and Lime Streaks		2240
Shale and Lime		2465
Lime		2528
Lime and Shale		3160
Lime		3190
Lime and Shale		3238
Lime		3595
Lime and Red Shale		3620
Conglomerate		3672
Dolomite		3700
Total Depth		3700

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.,

BY: *Kendell G. Peel*

SUBSCRIBED AND SWORN to before me this 5th day of November, 1951.

Bernice L. Irwin
Notary Public, Barton County, Ks.

My commission expires April 23, 1955. STATE OF KANSAS

RECORDING
FILE SEC. 21-14-18W
BOOK PAGE 124-14

NOV - 8 1951
COUNTY CLERK
BARTON COUNTY, KANSAS