


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 14 Twp. 14 Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines NW SE SE  
Lease Owner Woodman & Iannitti Drilling Co.  
Lease Name Brull Well No. 1  
Office Address 706 Union National Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-17 19 64  
Application for plugging filed 5-17 19 64  
Application for plugging approved 5-17 19 64  
Plugging commenced 5-17 19 64  
Plugging completed 5-17 19 64  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3580 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1168'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 480' w/ 20 sx cement  
Middle Plug @ 240' w/ 20 sx cement  
Top Plug @ 40' w/ 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

MAY 19 1964  
05-19-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Woodman & Iannitti Drilling Co.  
Address 706 Union National Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman  
706 Union National Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of May, 19 64

My commission expires Feb. 11, 1968  
Justina Chamberlain  
Justina Chamberlain Notary Public.

DRILLING LOG

Company: Woodman & Iannitti Drilling Co.  
 LEASE: #1 Brull  
 Sec. 14-14-18W  
 Loc. NW SE SE, Ellis County, Kansas

Contractor: Woodman & Iannitti Drilling Co.  
 706 Union Nat'l. Bldg.  
 Wichita, Kansas

Date Comm: May 8, 1964

Date Comp: May 17, 1964

Total Depth: 3580'

Casing: 8 5/8 @ 1168' w/500 sz. cement

D & A

Figures indicate the bottom of the formation

0'	40	Surface & Sand
40	180	Hard Sand & Shale
180	430	Shale
430	540	Shale & Stks. Sand
540	600	Shale
600	790	Sand
790	950	Red Bed & Shale
950	1100	Red Bed
1100	1156	Sand & Rock
1156	1169	Anhy.
1169	1200	Anhy.
1200	1360	Red Bed & Shale
1360	1490	Shale & Shello
1490	1815	Shale & Shello
1815	1890	Lime & Shale
1890	2080	Lime & Shale
2080	2230	Lime & Shale
2230	2350	Lime & Shale
2350	2465	Broken Lime
2465	2640	Lime & Shale
2640	2805	Lime & Shale
2805	2950	Lime & Shale
2950	3025	Lime
3025	3105	Lime
3105	3155	Lime
3155	3220	Lime
3220	3275	Lime
3275	3325	Lime
3325	3355	Lime
3355	3390	Lime
3390	3440	Lime
3440	3490	Lime
3490	3535	Lime
3535	3550	Shale & Cert
3550	3580	Dolomite
3580		Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 19 1964

CONSERVATION DIVISION  
 Wichita, Kansas

I certify the above to be a true and correct copy of the Driller's Log and the Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

By: K. T. Woodman  
 K. T. Woodman