

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#4  
 API NUMBER 15,051,23,862-00-00

LEASE NAME Hiatt-Madden

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

400 Ft. from S Section Line

4980 Ft. from E Section Line

SEC. 7 TWP. 14 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-27-88

Plugging Completed 4-28-88

LEASE OPERATOR Cattleman's Oil Operation

ADDRESS HC39, Box 74, Hays, Kansas 67601

PHONE# (913) 625-5394 OPERATORS LICENSE NO. 7064

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Four (4)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3867'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	800'	None
				5-1/2"	3765'	2,876.52'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3500' and 5 sacks cement. Shot casing at 2960' and 2800'. Pulled 70 joints of 5-1/2" casing. Allied squeezed well with 600# hulls and 200 sacks ATL cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
 (Address) Box 698, Great Bend, Ks. 67530

RECEIVED  
 SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 88  
 STATE CORPORATION COMMISSION

05-04-88  
 MAY 04 1988  
 My Commission Expires:

NOTARY PUBLIC  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 9-26-91

Jonas M. Leatherman  
 Notary Public