


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 7 Twp. 14S Rge. 18 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines C-SE SE SE
Lease Owner Sunray Oil Corporation
Lease Name KANSAS STATE 'A' Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 6 1952
Application for plugging filed Oct. 11 1952
Application for plugging approved Oct. 12 1952
Plugging commenced Oct. 6 1952
Plugging completed Oct. 6 1952
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3726 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-KC	Dry	3365	3590	8-5/8"	268'	None
Arbuckle	Water	3713	3726			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud. Set 8-5/8" plug at 240' with 20 sax cement on top of plug. Filled hole with mud & set 8-5/8" plug at 40 feet. Placed 1 sax of hulls on top of plug and then cemented to top of 8-5/8" surface casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Co.
Address Philower Bldg., Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. E. WESTBROOK, JR. (employee of owner XXXXXXXXXXXXXXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr. Engineer
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1952

Martha Scott
Notary Public.

My commission expires April 19, 1956

24-2675-S 2-52-20M

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1952
11-18-52
MISSION

PLUGGING
FILE SEC 7T4R182
BOOK PAGE 58 LINE 21

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
November 14, 1952

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: October 24, 1952
Drilling Completed: November 6, 1952

Kansas State "A" #1
SE-SE-SE-Sec. 7-14S-18W,
Ellis County, Kansas.

DRILLERS LOG

Surface Clay & Post Rock	0-215
Shale & Shells	215-750
Sand	750-975
Red Bed	975-1312
Anhydrite	1312-1350
Shale & Shells	1350-2245
Lime & Shale	2245-2729
Lime Shale & Shells	2729-2820
Broken Lime & Shale	2820-2930
Lime & Shale	2930-3075
Lime	3075-3135
Lime & Shale	3135-3265
Lime	3265-3310
Lime & Shale	3310-3350
Lansing Lime	3350-3413
Lime	3413-3635
Maraton	3635-3652
Cherty Conglomerate	3652-3695
Lime	3695-3715
Dolomite	3715-3725 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's Kansas State "A" #1 SE-SE-SE-Section 7-14S-18W, Ellis County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My Commission Expires

PLUGGING
FILE SEC 7-14-S-18W
BOOK PAGE 58 LINE 21

RECEIVED
OIL & GAS COMMISSION
TULSA, OKLA.
NOV 14 1952