

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 7 TWP. 14 RGE. 18 W  
Location as in quarters or footage from lines:  
NW NE NE

			X

Lease Owner Rupe Oil Company, Inc.  
Lease Name #1 Ft. Hays State Well No. 1  
Office Address P.O. Box 2273, 434 Ohio, Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed October 22, 1981  
Application for plugging filed October 22, 1981, verbally  
Plugging commenced 8:00 a.m. October 22, 1981  
Plugging completed 11:00 a.m. October 22, 1981  
Reason for abandonment of well or producing formation  
Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation N/A Depth to top N/A bottom N/A T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	20lb 236'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Plugged with 50-50 pozmix - 4% gel, 3% CaCl.

Set 1st Plug @ 720' with 70 sacks  
Set 2nd Plug @ 210' with 40 sacks  
Set 3rd Plug @ 40' with 10 sacks  
5 sacks rathole  
5 sacks mousehole

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1981

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. K. Morrison (employee of owner) or ~~(owner or operator)~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
555 N. Woodlawn, Bldg. 1 - Suite 207  
Wichita, KS. (Address) 67208

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 81

Suzanne P. Graef  
Notary Public.

My Commission expires: 10/26/85



October 28, 1981

CONTRACTOR'S WELL LOG

15-051-22597-0000

OPERATOR: Rupe Oil Company, Inc.  
 CONTRACTOR: KANDRILCO, Ltd.  
 WELL NAME: #1 Ft. Hays State  
 LOCATION: NW NE NE Section 7, T14S-R18W  
 Ellis County, KS  
 API NO.: 15-051-22,597  
 COMMENCED: October 11, 1981  
 COMPLETED: October 22, 1981

Drilled 259' of 12 1/4" hole. Set 236' of new 8 5/8" 20# casing at 236' with 175 sacks of common cement - 2% gel, 3% CaCl. Cement did circulate to surface. Plug was down at 5:00 a.m., October 12, 1981.

<u>FORMATION</u>	<u>TOP'</u>	<u>BOTTOM'</u>
Shells and Sand	0	259
Sand, Shells and Shale	259	1259
Lime and Shale	1259	2260
Shale and Lime	2260	3420
Lime and Shale	3420	3650
Lime and Chert	3650	3750

RTD 3750'. Plugged to abandon. Plugged with 50-50 Pozmix, 4% gel, 3% CaCl. Set 70 sacks at 720', 40 sacks at 210', 10 sacks at 40', 5 sacks rathole and 5 sacks mousehole. Plugging complete at 11:00 a.m., October 22, 1981.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:

I, C. K. Morrison, President, KANDRILCO, Ltd., do hereby state that the above is a true and correct copy of the Driller's Log for the Rupe Oil Company, Inc. #1 Ft. Hays State well located in Ellis County, Kansas.

KANDRILCO, Ltd.

*C. K. Morrison*


C. K. Morrison, President

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1981

CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 28th day of October, 1981.



*Suzanne P. Graef*  
Suzanne P. Graef - Notary Public

My Commission expires: October 26, 1985