

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat**

Ellis.....County. Sec. 5 Twp. 14S. Rge.(E) 18(W)
Location as "NE¼NW¼SW¼" or footage from lines.....N7C SE½
Lease Owner.....Darby Petroleum Corporation
Lease Name.....Kansas State Unit Well No. 1
Office Address.....1015 Philtower Bldg., Tulsa, 3, Oklahoma.
Character of Well (completed as Oil, Gas or Dry Hole).....Dry Hole
Date well completed.....February 19, 1944.....19
Application for plugging filed.....February 21, 1944.....19
Application for plugging approved.....February 23, 1944.....19
Plugging commenced.....February 19, 1944.....19
Plugging completed.....March 4, 1944.....19
Reason for abandonment of well or producing formation.....Dry Hole.

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. T. Alexander.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 3745..... Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole filled with mud 3745' to 300', bridge at 300' with cement to 255', mud and bridge 255' to 60', cement 60' to 6' and mud to surface.



STATE DEPARTMENT
WASHINGTON

MAR 11

03-11-44

(See reverse side for formation record)

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Darby Petroleum Corporation.....
Address.....1015 Philtower Building.....
.....Tulsa, 3, Oklahoma.....

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
W. H. Barclay (employee of owner) ~~is~~ attorney of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above
described well as filed and that the same are true and correct. So help me God.

(Signature)

1015 Philtower Bldg., Tulsa, 3, Oklahoma.
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of March 1944

My commission expires March 1, 1946.

Notary Public.

FORMATION RECORD

	<u>FROM</u>	<u>TO</u>
Shale & shells	0	480
Sand	480	580
Shale & shells	580	740
Sand	740	920
Shale & shells	920	1000
Redbed	1000	1260
Anhydrite	1260	1300
Redbed	1300	1340
Redbed & shale	1340	1550
Shale & shells	1550	1695
Salt	1695	1800
Shale & shells	1800	1955
Lime & shale	1955	2315
Lime	2315	2450
Lime & shale	2450	2495
Shale & shells	2495	2645
Lime	2645	2675
Shale & shells	2675	2715
Lime & shale	2715	2795
Shale & shells	2795	2860
Lime & shale	2860	3050
Shale & shells	3050	3080
Lime	3080	3090
Lime & shale	3090	3166
Lime	3166	3564
Lime & shale	3564	3656
Lime, shale & chert	3656	3690
Arbuckle Lime Lime & chat	3690	3711
Arbuckle Lime	3711	3745 TD.