

13-051-20075-00-01

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

01-22-1970

Operator's Full Name Bachus Oil Co.
Complete Address 721 E. Central Wichita, Kansas
Lease Name Ruder Well No. 1
Location NE NW NW Sec. 25 Twp. 14 Rge. (E) (W) 17
County Ellis Total Depth 3499
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated Washdown to 2110' New hole to TD (3499)
Plugging Contractor Abercrombie Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 4:30A Day 16 Month 1 Year 1970

The above well was plugged as follows:

RTD 3499' 8 5/8 csg set at 190' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mearns
Well Plugging Supervisor

DATE 1/22/70
INV. NO. 1293-W