

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION

JUL 05 1977

07-05-1977  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 151 - 21,354 - 00 - 00 (of this well)

Operator's Full Name Eureka Petroleum Co. & Parrish Oil Co.

Complete Address 110 N. Market, Suite 206 Litwin Bldg., Wichita, Kansas

Lease Name Schumacher Well No. 1

Location SW NW SW Sec. 23 Twp. 14 Rge. (E) (W) 17

County Ellis Total Depth 3550'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 4 A Day 30 Month 6 Year 1977

The above well was plugged as follows:

RTD 3550' 8 5/8 csg set 208' cwc 130 sk. Plg. Mat. 50-50. poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 7-5-77

INV. NO. 5423-W