

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22006-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name WELSO CASING PULLING

Complete Address BOX 176 CHASE, MANA. 67526

Lease Name GABEL Well No. #1

Location C-E 1/2 - NE - 1/4 <sup>NESENE AND C&C</sup> Sec. 19 Twp. 14 Rge. 17 (East) (West)

County ELLIS Total Depth 3560 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor WELSO CASING PULLING (MILLARD WELSO)

Address BOX 176 CHASE, MS. 67526 License No. 683

Operation Completed: Hour: 3:45 PM Day: 22 Month: FEB. Year: 19 81

The above well was plugged as follows:

8 5/8" 225 FT S.P. CUMUL / 125 ST CMT. 5 1/2" SET @ 3560 FT CUMUL / 100 ST CMT.

PERF'S - TOP. 3413 FT -> PLUG. BACH. 3500 FT -> SAND BOTTOM TO 3363 + 1/5 CMT.

SHOT PIPE TWICE -> RECOVERED 2826 FT.

ORDERED - 140 ST 50% Pozmix 6% GEL - 3% CA-CL -> 19 ST GEL -> 5 ST HULLS + 8 5/8" PLUG.

PUMPED IN 8 5/8" WITH PUMP TRUCK -> 4 ST HULLS -> 15 ST GEL.

60 ST CMT. -> 2 ST GEL. AND 80 ST CMT.

MAX. PRESSURE. 900 LBS TO 450 LBS

RECEIVED  
CEMENTED BY: ALLIED OILFIELD

FEB 24 1981

02-24-1981

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

3-13 81  
4978W

Signed: Millard Welso  
Conservation Division Agent