

15-051-00578-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW SW

SEC. 35 TWP. 14 RGE. 18

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Dechant \_\_\_\_\_

Operator The Globe Oil & Refg Co. Address 301 S Market Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3683 Feet.

Plugging Contractor Lewis Drg Co & Sun Cementing Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 320' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug

at 500', displaced 25 sax cement through drill pipe, heavy mud to

300', set cementing plug, displaced 25 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10

sax cement to bottom cellar.

*Leon Betty*

District Conservation Agent

Date 8-12-57

PLUGGING  
FILE SEC 35 T. 14 R. 18W  
BOOK PAGE 37 LINE 2

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1957  
08-13-57  
CONSERVATION DIVISION  
Wichita, Kansas