

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Black Petroleum, Inc.

Complete Address 445 Olive W. Garvey Bldg., Wichita, Kansas 67202

Lease Name Pfannenstiel Well No. 1

Location SW NE NE Sec. 35 Twp. 14 Rge. 1 (E) 1 (W) 18

County Ellis Total Depth 3665

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Woodman-Iannitti

Address Wichita, Kansas License No.       

Operation Completed: Hour 10:15A Day 13 Month 3 Year 1970

The above well was plugged as follows:

RTD 3665' 8 5/8 csg set at 240' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing  
Well Plugging Supervisor

DATE 3/19/70  
INV. NO. 1613-4