

15-051-00371-00-00 RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1959
CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

12-11-59

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE NE NW Sec. 29 Twp. 14 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3730

I have this date completed supervision of plugging of:

Lease Name: Engel Well No. 1

Operator's Full Name: Alpine Oil & Royalty

Complete Address: 800 Bitting Bldg Wichita, Kans

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 342

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 6 Month 12 Year 59

The above well was plugged as follows:

8 5/8" 175' circulated with cement - 5 1/2" 3729' with 150 sax cement behind.

PB to 3640', perforated 3555'.

Filled with sand to 3540', set 5 sax cement with dump bailer, pulled

2913' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550',

Ø 23 sax (Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud

to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to

35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 549-u