

4

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas

Lease Name Mary Engle Well No. 2*D

Location SE SE/SE Sec. 27 Twp. 14 Rge. (E) (W) 18

County Ellis Total Depth 3677'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:15P Day 21 Month 8 Year 1969

The above well was plugged as follows:

RTD 3677' 8 5/8 csg set at 281' cwc Cmt. "at. 50-50 poz cmt. W6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/69
INV. NO. 376-W

Signed: [Signature]
Well Plugging Supervisor