



15-053-20113-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

December 28, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Ensminger of American Drilling Corp., Ltd has this date requested permission to plug the following described well:

Mr. Ensminger guarantees payment of the plugging fee.

Operator's full Name: Bell & Rupe

Complete Address: 222 Brown Bldg., Wichita, Kansas 67202

Lease Name: Vopat "C" Well No. 1

Location: C W/2 NE SW Sec. 23 Twp. 14 Rge. 10 (E)(W) X

County: Ellsworth Total Depth 3275' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ensminger was instructed to plug the well as follows:

Fill hole with mud to 265'. Push plug and 1/4 sack hulls to 265' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent