



15-053-20210-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

September 16, 1971

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. C. Ogle of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: L. V. Stan Bell

Complete Address: Suite 925, 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Sibrava Well No. 1

Location: NW SE NE Sec. 18 Twp. 14 Rge. 10 (W) X


County: Ellsworth Total Depth 2870' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

Fill hole with mud to 245'. Push plug and 1/4 sack hulls to 245' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent