



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 2137 Market  
WICHITA, KANSAS 67202

RECEIVED  
MAY 9 1968  
CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

May 7, 1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Ensminger of American Drilling Corporation has this date requested permission to plug the following described well:

Mr. Ensminger guarantees payment of the plugging fee.

Operator's full Name: Will P. Ash

Complete Address: 507 Rutland, Wichita, Kansas

Lease Name: Hunter Well No. 1

Location: SE SW NW Sec. 18 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 2860' Oil Well       

Gas Well        Input Well        SWD Well        D & A -X Lost Hole       

Mr. Ensminger was instructed to plug the well as follows:

Fill hole with mud to 270'. Push plug and 1/4 sack hulls to 270' and  
cement hole with 25 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

[Signature]  
Conservation Division Agent