

State of Kansas



15-053-20392-00-00

RECEIVED
STATE CORPORATION COMMISSION
State Corporation Commission
JAN 20 1975
CONSERVATION DIVISION
(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
Wichita, Kansas WICHITA, KANSAS 67217

December 20, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Wilson Exploration & Dev. has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Jack Bock

Complete Address: 521 South 14th St., Lincoln, Nebraska

Lease Name: Virginia E. Vopat Well No. 1

Location: W/2 SW SW Sec. 14 Twp. 14 Rge. 10 XX (E) (W) X

County: Ellsworth Total Depth 3000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks
cement through drill pipe at 500'. Pump 25 sacks cement
through drill pipe at 240'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Bridge rathole and
cement with 2 sacks cement.

Very truly yours,

Arthur J. Loren
Conservation Division Agent