



15-053-20303-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

October 23, 1972

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 27 1972  
10-27-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Herren of H-30, Inc. has this

date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: L. V. Stan Bell

Complete Address: 562 Wetmore Court, Wichita, Kansas

Lease Name: Soukup Well No. 1

Location: C W/2 SE NW Sec. 14 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 2980' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Herren was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent