

State of Kansas



15-053-20464-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

April 27, 1977

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 06 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Odin of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Odin guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 908 Union Center, Wichita, Kansas 67202

Lease Name: Hlaus Well No. 1

Location: NW NW SE Sec. 9 Twp. 14 Rge. 10 (E) (W) X


County: Ellsworth Total Depth 3487' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Odin was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe
at 500'. Pump 25 sacks cement through drill pipe at 250'.
Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent