

State of Kansas



15-053-20432-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

March 21, 1976

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 02 1976

04-02-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. John Scarbrough of Thomas Drilling Company has this date requested permission to plug the following described well:

Mr. Scarbrough guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center, Wichita, Kansas 67202

Lease Name: Vancura Well No. 1

Location: SE SW SW Sec. 7 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 3331' Oil Well

Gas Well Input Well SWD Well D & A. X Lost Hole

Mr. Scarbrough was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 260'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent