

15-053-30159-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
November 17, 1966
CORPORATION COMMISSION

NOV 22 1966
11-22-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Banks of Isern Drilling Company has this
date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Isern-Wells

Complete Address: P.O. Box 486, Ellinwood, Kansas

Lease Name: Bartunek Well No. 1

Location: C SW $\frac{1}{4}$ Sec. 4 Twp. 14 Rge. 10 (E) (W) X

County Ellsworth Total Depth 3435' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

Fill hole with mud to 280'. Push plug and $\frac{1}{4}$ sack hulls to 280' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Arthur J. Loman
Conservation Division Agent