



15-053-20389-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

December 4, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Wilson Exploration & Development has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Borrel Oil Company

Complete Address: Box 391, Wilson, Kansas

Lease Name: Albert Vopat Well No. 1

Location: NE NE SE Sec. 35 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 3115' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks
cement through drill pipe at 500'. Pump 25 sacks cement
through drill pipe at 215'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Bridge rathole and
cement with 2 sacks cement.

Very truly yours,

Stallman J. Loman
Conservation Division Agent