

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

November 12, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1979

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Wilson Exploration & Drilling has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Wilson Exploration Drilling, Inc.

Complete Address: Drawer 546, Wilson, Kansas

Lease Name: KaneK Well No. 5

Location: NE NE NW Sec. 35 Twp. 14 Rge. 10 (W) X

County: Ellsworth Total Depth 2830' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

8 5/8" - 231' cem. circ. Fill hole with mud. Pump 40 sacks
Cement through drill pipe at 500'. Pump 25 sacks cement
through drill pipe at 225'. Push plug and 1/2 sack hulls
to 40' and cap hole with 10 sacks cement. Bridge rat hole
and cement with 2 sacks cement

Very truly yours,

Arthur J. Lomen
Conservation Division Agent