

State of Kansas



15-053-20449-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

August 23, 1976

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 26 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. John Ball of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Ball guarantees payment of the plugging fee.

Operator's full Name: Borell Oil Company

Complete Address: Box 391, Wilson, Kansas

Lease Name: Vanek Well No. 4

Location: NE SW NW Sec. 35 Twp. 14 Rge. 10 (E) (W) X


County: Ellsworth Total Depth 2852' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ball was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 220'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent