



15-053-20410-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

September 14, 1975

VERBAL PERMIT FORM
(To Be Filed By, Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Borell Oil Company

Complete Address: Box 391, Wilson, Kansas 67490

Lease Name: Vanek Well No. 3

Location: SE SE NW Sec. 35 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 2833' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crawford was instructed to plug the well as follows:

Hole filled with mud. Pump 50 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 200'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent