

To: 1 090087
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-12
API NUMBER 15- 071-20,520 - 0000
C NE NE, SEC. 16, T. 18 S, R. 40 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3691
Operator: Brock Resources, Inc.
Name & Address: 25th & Vine St.
Dean Ellner Bldg., Suite 2
Hays, KS 67601

Lease Name Vogt "A" Well # 1
County Greeley 99.12
Well Total Depth 3050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1720

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:30 a.m. Day: 12 Month: 6 Year: 19 91

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 3049' w/250 sx cement, PBSD 3030', Perfs at 2935-65'
1st plug pump 1 sx hulls and 20 sx cement to 2800',
2nd plug pump 50 sx cement at 1730',
3rd plug pump 30 sx cement at 600',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:30 p.m. Day: 12 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 20 sx cement to 2800',
2nd plug pulled to 1730' and pumped 50 sx cement,
3rd plug pulled to 600' and pumped 30 sx cement,
4th plug pulled to 40' and pumped 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 1905' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (old) observe this plugging.

DATE 6-20-91

WV. NO. 32197

6-12

Signed _____
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1991
6-17-91
CONSERVATION DIVISION
Wichita, Kansas