

1080308

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,525-0000
C SE/4 SEC. 22, T 18 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 1340 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1300 FEET FROM ~~WEST~~^{EAST} SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HAMPTON UNIT WELL # 1

TECHNICIAN'S PLUGGING REPORT 5/18 COUNTY GREELEY 97.50

OPERATOR LICENSE # 3555 WELL TOTAL DEPTH 3000 FEET

OPERATOR: GLEN S. SODERSTROM PRODUCTION CSG: SIZE 4 1/2" @ 3000' WITH 850 SX

NAME AND PO BOX 822663 SURFACE CASING: SIZE 8 5/8" @ 284' WITH 190 SX

ADDRESS DALLAS, TX 75382

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 18 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 2880-96, 2911-17

PUMPED DOWN 4 1/2" 200# HULLS AND 190 SX CEMENT. MAXIMUM PRESSURE AT 600#. SHUT IN AT 300#.

PUMPED DOWN 8 5/8" x 4 1/2" ANNULUS 10 SX CEMENT. SHUT IN AT 300#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:10 PM DAY: 18 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 4 1/2" 200# HULLS AND 190 SX CEMENT. MAXIMUM PRESSURE AT 600#. SHUT IN WITH 300#

PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 10 SX CEMENT. SHUT IN AT 300#.

RECEIVED STATE CORPORATION COMMISSION

3-24-00 MAY 24 2000

REMARKS: USED 65/35 POZMIX 4% GEL BY SWIFT SERVICES. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING. SIGNED

Kevin D. Shurt (TECHNICIAN)

FORM CP-2/3

INVOICED DATE 5/25/00 INV. NO. 61779

Handwritten signature and initials