

To: 1 071080
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-11

API NUMBER 15- 071-20,565-0000 216R
SW SW NW, SEC. 22, T. 18 S, R. 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30994

Operator: Leede Oil & Gas, Inc.
Name & Address 6400 S. Fiddlers Green Circle, #2100
Englewood, CO 80111

Lease Name Williams Well # 1-22
County Greeley 172.25
Well Total Depth 5300 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 11 Month: 7 Year: 19 92

Plugging proposal received from Bernie Myer

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2541'

1st plug at 2560' with 50 sx cement, 2nd plug at 1500' with 50 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 340' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 p.m. Day: 11 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2560' with 50 sx cement,

2nd plug at 1500' with 50 sx cement,

3rd plug at 800' with 50 sx cement,

4th plug at 340' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXX) did not observe this plugging.

DATE AUG 07 1992

INV. NO. 35885

Signed Dan Goodrow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1992
7-15-92
CONSERVATION DIVISION
Wichita, Kansas