

To: <sup>1</sup> 031265  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-12 API NUMBER 15- 071-20,621-0000

C NW NW, SEC. 19, T 18 S, R 42 W ~~EX~~  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31155

Lease Name Betty J Well # 4-19

Operator: Axem Resources Inc.  
Name &  
Address 7800 E. Union Ave., Ste. 1100  
Denver, CO 80237

County Greeley  
Well Total Depth 5250 <sup>1170' ✓</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 4 p.m. Day: 12 Month: 3 Year: 19 94

Plugging proposal received from D.L. Finnessy

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2552-82'  
1st plug at 2560' with 50 sx cement, 2nd plug at 1710' with 80 sx cement,  
3rd plug at 900' with 50 sx cement, 4th plug at 330' with 40 sx cement,  
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 8 p.m. Day: 12 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 2560' with 50 sx cement,  
2nd plug at 1710' with 80 sx cement, 3rd plug at 900' with 50 sx cement,  
4th plug at 330' with 40 sx cement, 5th plug at 40-0' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel <sup>1/4</sup># floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

(~~XXX~~ / did not) observe this plugging.

INVOICED  
DATE 3-22-94  
INV. NO. 40128

Signed Steve Durrant (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 18 1994  
3-18-94  
CONSERVATION DIVISION  
Wichita, Kansas