

To: 1 090883

API NUMBER 15- 071-20,676 -0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

App. SW NW NE, SEC. 17, T 18 S, R 42 W/X
1200 feet from NX section line
2259 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 32179

Lease Name Petriello Well # 1

Operator: Hollis R. Sullivan, Inc.

County Greeley 173.88

Name & Address P.O. Box 2506

Well Total Depth 5350 feet

Wichita Falls, TX 76307

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS. 67202

Company to plug at: Hour: _____ Day: 30 Month: 11 Year: 19 97

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

was: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2600' with 50 sx cement, 2nd plug at 1600' with 80 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 330' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:30 p.m. Day: 30 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2600' with 50 sx cement,

2nd plug at 1600' with 80 sx cement, 3rd plug at 800' with 40 sx cement,

4th plug at 330' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1997

INV. NO. 49627

Rec'd 1-29-98

JAN 29 1998

Signed _____ (TECHNICIAN)