

To: 1 051521  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-8

API NUMBER 15-071-20,555-0000 117 R

App. NE SE NE, SEC. 17, T. 18 S, R. 42 W/E

3526 feet from S section line  
130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3317

Lease Name Bounds Well # 1-17

Operator: Beard Oil Company  
Name &

County Greeley 174.68

Address 5600 N. May Ave., Ste. 200  
Oklahoma City, OK 73112

Well Total Depth 5375 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 8 Month: 1 Year: 19 92

Plugging proposal received from Ed McKinna

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2559'

1st plug at 2580' with 50 sx cement, 2nd plug at 1680' with 80 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 8 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2580' with 50 sx cement,

2nd plug at 1680' with 80 sx cement, 3rd plug at 800' with 50 sx cement,

4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

INVOICED

DATE JAN 29 1992

34391

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
1-28-92  
JAN 28 1992

CONSERVATION DIVISION  
WICHITA, KS