

To: 1 080147 10-1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,173 - 0000
C NW NE, SEC. 36, T 18 S, R 40 W/4
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7040
Operator: Dernick Resources, Inc.
Name & Address: 515 W. Greens Rd., Ste. 1150
One Commerce Green
Houston TX 77067

Lease Name Helm Well # 2
County Greeley 95.97
Well Total Depth 2953 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 2:30 p.m. Day: 1 Month: 10 Year: 1997

Plugging proposal received from Dave Olson

(company name) Dernick Resources, Inc. (phone) 316-376-4400

were: 4 1/2" at 2953' w/500 sx cement. PBD 2920'. Perfs at 2906-2910'

1st plug pump 300 lbs. hulls and 150 sx cement down 4 1/2" casing,

Check backside.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 1 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 150 sx cement down 4 1/2" casing.

Maximum pressure 500 psi and shut in 500 psi.

2nd plug went down 8 5/8" X 4 1/2" and pumped 15 sx cement. Pressured up to 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE ~~OCT 23 1997~~

Signed Kevin P Strube
(TECHNICIAN)

INV. NO. 49262 JAN 09 1998