

1030219

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,320-0000

SW SW SW, SEC. 35, T 18 S, R 40 W/EX

330 feet from ~~XX~~/S section line

330 feet from W/~~EX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6085

Lease Name Helm Well # 1

Operator: Smith Cattle, Inc.

County Greeley

Name & Address Box 399

Well Total Depth 2250 ^{77.13} feet

Tribune KS 67879

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling License Number 5382

Address West Highway 50, Garden City, KS 67874

Company to plug at: Hour: 8:00 am Day: 2 Month: July Year: 19 84

Plugging proposal received from Claud Norwood

(company name) Cheyenne Drilling (phone) 316-277-2062

were: Complete drill string stuck in hole at 2250 - Nitrogen blow-out est. at 60 MCFD -

Well blew for 3 weeks. Perf - drill pipe at 1710' - Parted casing fell 4' & stopped flow
of gas and put well on vacuum.

1st plug pumped 100 sx & waited 3 hrs. Test for cement - none

2nd plug pumped 300 sx & shut in over night - no fill up. Could still pump into casing
next morning. Fluid level at 520'.

Plugging Proposal Received by Steve Alenart
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:20 pm Day: 3 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 3rd plug loaded annulus with 160 bbls of drilling mud to condition

hole & pumped 200 sx hot cement with flow seal and shut in for 3 hrs. Top cement at 667'.

4th plug perforated pipe at 657' with 2 shots & broke circulation with water and pumped

175 sx hot cement with flow seal & circulated well to surface.

RECEIVED
STATE CORPORATION COMMISSION
7-6-84
JUL 06 1984

Remarks: Used Common Class H cement 2% gel 3% cc with flow seal by Halliburton
(If additional description is necessary, use BACK of this form)

INVOICED

(If you observe this plugging.

DATE 7-13-84

Signed Steve Alenart
(TECHNICIAN)

INV. NO. 2477

7-3