

2-16-88

2040389

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-21,130 -00-00

NE NW, SEC. 3, T 35 S, R 5 W/EX

4620 feet from S section line

3300 feet from E section line

Lease Name Rolland Well # 1

County Harper 169.55

Well Total Depth 5217 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 408

TECHNICIAN'S PLUGGING REPORT

Operator License # 8465

Operator: Ceja Corporation

Name & Address 4400 One Williams Center

Tulsa, OK 74172

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Shebester-Bechtel License Number \_\_\_\_\_

Address Blackwell, Oklahoma

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Kent Fisher

(company name) Ceja Corporation (phone) \_\_\_\_\_

were: PBTD 5193' Perfs 4856-72, 4896-4902, 4930-60, 5014-28, 4878-88, 4918-22,

4980-90, 5054-70 4 1/2" @5216 CIBP 4800, Mud below CIBP, Mud to surface,

perf @460' Bullhead down 4 1/2" casing, back up 8 5/8" annulus

Plugging Proposal Received by Phil Worley (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 22:50 Day: 16 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT

Nine pound mud was pumped down 4 1/2" casing to cover perfs. A

CIBP was set @4780'. Tubing was run in the 4 1/2" casing to CIBP. Four sxs

cement was spotted on top of CIBP. Pulled 2 joints of tubing and circulated

4 1/2" casing with 9\* drill mud. Perfed 4 1/2" casing @460' and circulated 4 1/2"-

8 5/8" annulus with cement.

Remarks: Dowell-Schlumber J#03-16-2951 (if additional description is necessary, use BACK of this form.)

INVOICED

CONSERVATION COMMISSION did not observe this plugging.

DATE 2-22-88 FEB 19 1988

Signed [Signature] (TECHNICIAN)

ENV. NO. 19905 CONSERVATION DIVISION

2-16 MAR 24 1988