

15-185-12302-00-00

1 080327

Docket No. D-02,905

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 8-6-51

TECHNICIAN'S PLUGGING REPORT

SW NE NE, SEC. 7, T 21 S, R 14 (W) X

4290 feet from S section line
990 feet from E section line

Operator License # 5565

Lease Name Frey "A" Well # #5 SWD

Operator: National Cooperative Refinery Assoc. County Stafford 136.96

Name & Address P. O. Box 6

Well Total Depth 4214 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 880

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 pm Day: 14 Month: February Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3902' PBSD 4140' Well Bridged at 2400'

1st plug squeeze 5 1/2" with 200 sx cement mixed with 3 sx hulls.

Pump 200 sx cement mixed with 1 sack hulls on back side.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 pm Day: 14 Month: February Year: 19 85

ACTUAL PLUGGING REPORT squeezed 5 1/2" with 200 sx cement mixed with 3 sx hulls.

Maximum pressure 200 psi and shut in pressure 0. Pumped 200 sx cement mixed with 1 sack hulls down back side. Maximum pressure on back side 400 psi and shut in 0.

2-15-85 Cut 8 5/8" & 5 1/2" off and checked cement. Tagged cement at 650'. No fluid.

Filled back side and 5 1/2" with Redi-Mix to top. (Used 6 1/2 yards) Thin MIX (160)

RECEIVED STATE CORPORATION COMMISSION

Remarks Used 60/40 Pozmix 2% gel 3% cc by Allied. No Recovery (If additional description is necessary, use BACK of this form.) FEB 25 1985 2-25-85

INVOICED (did not observe this plugging.)

DATE 2-27-85

Signed J. H. Metz (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 7173