

9-6

To: 1 051084  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-171-20,374-00-00

C NE SE, SEC. 16, T 19 S, R 33 W/E

1960 ~~1980~~ feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Hutchins Well # 1-16

Operator: Landmark Oil Exploration, Inc.

County Scott 152.75

Name & Address 110 South Main, Suite 510

Well Total Depth 4700 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Warrior Drilling Company License Number 5883

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 5 Month: 9 Year: 19 88

Plugging proposal received from Marrion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2220'

1st plug at 2220' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:45 a.m. Day: 6 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 12 1988  
9-12-88

CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Drey  
(TECHNICIAN)

**INVOICED**  
I (did not) observe this plugging.

DATE 9-14-88

REV. NO. 22237