

9-30

1 031106

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,524-0000

NE NW SW, SEC. 14, T 18 S, R 43 W/E

2130 feet from S section line

3255 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Linn Well # 1

Operator: Amoco Production Company

County Greeley 172.25

Name & Address P.O. Box 800, Rm 1833

Well Total Depth 5300 feet

Denver, CO 80201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 502

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Exeter Drilling Company License Number 3098

Address P.O. Box 17349, Denver, CO 80217

Company to plug at: Hour: 7 p.m. Day: 30 Month: 9 Year: 19 90

Plugging proposal received from R.J. Prescott

(company name) Exeter Drilling Company (phone) 303-861-0181

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1710' with 80 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 500' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 30 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2640' with 50 sx cement,

2nd plug at 1750' with 80 sx cement,

3rd plug at 850' with 50 sx cement,

4th plug at 530' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 10 sx cement,

7th plug to circulate mousehole with 5 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Dowell.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
10-4-90
OCT 4 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 10-10-90

INV. NO. 29608
9-30