

120221

2-27

138 P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. 200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,467-0000
S/2 SW, SEC. 14, T 18 S, R 43 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

550 feet from S section line
3720 feet from E section line

Operator: Murfin Drilling Company
Name & Address: 250 North Water, Suite 300
Wichita, KS 67202

Lease Name Gould Well # A#2
County Greeley 172.90

Well Total Depth 5320 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 6:30 a.m. Day: 27 Month: 2 Year: 19 89

Plugging proposal received from Matt Finnesey

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3896'
Anhydrite 2728-60'
1st plug at 2750' with 50 sx cement, 2nd plug at 1700' with 80 sx cement,
3rd plug at 470' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12 p.m. Day: 27 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2750' with 50 sx cement,

2nd plug at 1700' with 80 sx cement,

3rd plug at 470' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 03 1989 3-3-89 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 3-6-89

INV. NO. 24057

2-27