

1 051707

8-9

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
2200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,605-0000
161' NE of
C NW NE, SEC. 14, T. 18 S, R. 43 W/E
520 feet from N~~X~~ section line
1900 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606
Operator: Murfin Drilling Company, Inc.
Name & Address: 250 N. Water, Ste. 300
Wichita, KS 67202

Lease Name Moore-Johnson Well # 3
County Greeley 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 9 Month: 8 Year: 19 93

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Co. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2595-2626'

- 1st plug at 2620' with 50 sx cement, 2nd plug at 1550' with 80 sx cement,
- 3rd plug at 750' with 50 sx cement, 4th plug at 340' with 40 sx cement,
- 5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
- 7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 9 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2620' with 50 sx cement,
2nd plug at 1550' with 80 sx cement,
3rd plug at 750' with 50 sx cement,
4th plug at 340' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

1 ~~XXXXX~~ did not observe this plugging.

DATE: AUG 18 1993

INV. NO. 38384

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1993
8-12-93