

To: 1 040653 S-1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,561-0000  
SW NW SW, SEC. 13, T. 18 S, R. 43 W/E  
1980 feet from S section line  
330 feet from W EX section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30868  
Operator: MW Petroleum Corporation  
Name & Address 1700 Lincoln, Ste. 1900  
Denver, CO 80203-4519

Lease Name Sell Well # 13-31  
County Greeley 172.25  
Well Total Depth 5300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 514

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling Company License Number 5382  
Address P.O. Box 916, Garden City, KS 67846-0916

Company to plug at: Hour: 9 p.m. Day: 30 Month: 4 Year: 19 92

Plugging proposal received from Jake Kaffman  
(company name) Cheyenne Drilling Company (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2100'

1st plug at 2600' with 50 sx cement, 2nd plug at 1700' with 80 sx cement,  
3rd plug at 850' with 50 sx cement, 4th plug at 540' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 12:30 a.m. Day: 1 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2602' with 50 sx cement,  
2nd plug at 1700' with 80 sx cement, 3rd plug at 850' with 50 sx cement,  
4th plug at 540' with 50 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (XXX, did not) observe this plugging.

DATE MAY 21 1992  
INV. NO. 35308

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
MAY 4 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas