

1 051785

2-20

API NUMBER 15-071-20,615-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. NW SW, SEC. 12, T 18 S, R 43 W/4E

1880 feet from S section line

560 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

31155

Operator License # _____

Axem Resources Inc.

Operator Name: _____

Address 7800 E. Union Ave., Ste. 1100

Denver, CO 80237

Lease Name Annabel Well # 1-12

County Greeley

Well Total Depth 5300 172.25 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8.5/8 feet 318

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 2 a.m. Day: 20 Month: 2 Year: 19 94

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-3518

Remarks: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2506-2530'

1st plug at 2530' with 50 sx cement, 2nd plug at 1750' with 80 sx cement,

3rd plug at 850' with 50 sx cement, 4th plug at 350' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:45 a.m. Day: 20 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 2530' with 50 sx cement,

2nd plug at 1750' with 80 sx cement, 3rd plug at 850' with 50 sx cement,

4th plug at 350' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE FEB 25 1994

INV. NO. 40039

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1994
2-24-94
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)