

To: 1 031135
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-16 162P
API NUMBER 15-071-20,538-0000
App. C S/2
SE NW, SEC. 23, T 18 S, R 43 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9855
Operator: Grand Mesa Operating Company
Name & Address 200 E First St., Suite 307
Wichita, KS 67202

3150 feet from S section line
3300 feet from E section line
Lease Name Bounds Well # 1-23
County Greeley 171.43
Well Total Depth 5275 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Norseman Drilling, Inc. License Number 3779

Address 307 Emrs. & Bkrs. Bldg., 200 E.1st St., Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 16 Month: 1 Year: 19 91

Plugging proposal received from Rod Vaughn
(company name) Grand Mesa Operating Company (phone) 316-265-3000

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2555-80'
1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1650' with 80 sx cement,
3rd plug at 900' with 40 sx cement,, 4th plug at 540' with 40 sx cement,
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:45 a.m. Day: 16 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2580' with 50 sx cement,
2nd plug at 1650' with 80 sx cement,
3rd plug at 900' with 40 sx cement,
4th plug at 540' with 40 sx cement,
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I (XXXX) did not observe this plugging.
DATE 2-11-91
INV. NO. 30665

Signed Steve Durrant SD
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
1-25-91
JAN 25 1991