

1 080107

3-13

API NUMBER ~~15-07-20542-00-00~~

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

W/2 NW NW, SEC. 23, T 18 S, R 43 W/2
660 feet from NXX section line
330 feet from WXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9427

Lease Name Bounds A Well # 1

Operator: HGB Oil Co. C/O Sharp Engineering
Name & Address: P.O. Box 122
Andover, KS 67002

County Greeley 169.65
Well Total Depth 5220 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384, Ness City, KS 67560-0384

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 3 Year: 19 97

Plugging proposal received from Gary Sharp

(company name) Sharp Engineering (phone) 316-262-3596

logs: 5 1/2" at 5219', FO tool at 2643' cemented with 925 sx cement, open perms at 5126-29'
CIBP at 2700'

1st plug run tubing to 900' and pump 20 sx cement,

2nd plug pull tubing to 40' and circulate cement to surface.

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 3 Year: 1997

ACTUAL PLUGGING REPORT 1st plug ran tubing to 900' and pumped 20 sx cement,

2nd plug pulled tubing to 55' and circulated cement to surface,

3rd plug pumped 10 sx cement down 8 5/8" X 5 1/2". Maximum pressure 300 psi.

RECEIVED
KANSAS CORP COMM
3-30-98
11:39

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE _____
INV. NO. 47783

Signed Kevin P. Shuck (TECHNICIAN)